





LEGEND	ROAD AUTHORITY SHALL APPROVE USAGE OF THIS TGS		 GOVERNMENT OF WESTERN AUSTRALIA																		
<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;">  WORK AREA </div> <div style="border: 1px solid black; padding: 5px;"> <h3 style="text-align: center; margin: 0;">VMS MESSAGES</h3> <div style="display: flex; justify-content: space-around; margin: 5px 0;"> <div style="background-color: black; color: yellow; padding: 10px; text-align: center; width: 40%;"> BURNING OFF AHEAD </div> <div style="background-color: black; color: yellow; padding: 10px; text-align: center; width: 40%;"> MOBILE PLANT AHEAD </div> </div> <p style="color: red; font-weight: bold; margin: 0;">VMS ARE OPTIONAL AND MESSAGES MAY CHANGE TO SUIT WORKS. REFER TO TABLE A FOR MINIMUM DISTANCE TO BE INSTALLED FROM FIRST TEMPORARY WORK SIGN</p> </div>	<div style="text-align: center;">  </div>																				
GENERAL NOTES: <ol style="list-style-type: none"> THIS TGS IS ONLY TO BE USED AS PART OF THIS GENERIC TRAFFIC MANAGEMENT PLAN WHEN USING MMS ENSURE TWO 5mm THICK CORE FLUTE SIGNS ARE USED BACK TO BACK IN THE FRAME TO HELP PREVENT THE SIGN FROM BLOWING OUT THE WORKER SYMBOLIC SIGNS SHALL BE INSTALLED ONLY WHEN ON-FOOT PERSONNEL WILL BE VISIBLE TO PASSING TRAFFIC, OTHERWISE REPLACE WITH BURNING OFF OR SMOKE HAZARD SIGN ADVANCED WARNING VEHICLE SHALL BE STOPPED ALONG CURVED OR CRESTED SECTIONS OF ROAD WHERE VISIBILITY IS RESTRICTED TO MAINTAIN MINIMUM SIGHT DISTANCE GIVEN IN TABLE B WHERE SIGHT DISTANCE IS POOR FOR OPPOSING TRAFFIC, MOVE THE LEAD VEHICLE BEYOND DISTANCES GIVEN IN TABLE C TO MAINTAIN MINIMUM SIGHT DISTANCES GIVEN IN TABLE B WORKERS ON FOOT SHALL MAINTAIN A MINIMUM OF 1.2m CLEARANCE FROM THE TRAFFICABLE LANE AT ALL TIMES WORK PLANT SHALL ONLY TEMPORARILY ENCROACH ONTO THE TRAFFICABLE LANE WHEN SAFE WITH NO APPROACHING TRAFFIC 	<table border="1" style="width: 100%; border-collapse: collapse;"> <caption>TABLE 3.2 – SIGHT DISTANCE TO TRAFFIC MANAGENT VEHICLES</caption> <thead> <tr> <th>POSTED SPEED (km/h)</th> <th>MINIMUM SIGHT DISTANCE</th> </tr> </thead> <tbody> <tr> <td>≤ 60</td> <td>150m</td> </tr> <tr> <td>≥ 70</td> <td>250m</td> </tr> </tbody> </table> <p style="font-size: small; margin-top: 5px;">Minimum sight distance to be maintained from approaching traffic to convoy vehicles – excluding the work vehicle</p>			POSTED SPEED (km/h)	MINIMUM SIGHT DISTANCE	≤ 60	150m	≥ 70	250m												
POSTED SPEED (km/h)	MINIMUM SIGHT DISTANCE																				
≤ 60	150m																				
≥ 70	250m																				
DISCLAIMER: IT IS THE RESPONSIBILITY OF THE USER OF THIS TRAFFIC GUIDANCE SCHEME TO CONFIRM THE APPROPRIATENESS OR OTHERWISE FOR THE INTENDED WORK SITE BASED ON RIGOROUS RISK ASSESSMENT AND REVIEW OF THE REQUIREMENTS OF THE AS1742.3 AND MAIN ROADS WA TRAFFIC MANAGEMENT FOR WORKS ON ROADS CoP AND THE AGTMM. ALL RESPONSIBILITY WILL REMAIN WITH THE USER TO ENSURE COMPLIANCE WITH RELEVANT STANDARDS AND THE PROVISION OF THE NECESSARY LEVEL OF PROTECTION FOR WORK PERSONNEL AND WORK SITE.	<table border="1" style="width: 100%; border-collapse: collapse;"> <caption>TABLE 3.1 – EXCLUDING SHADOW VEHICLE</caption> <thead> <tr> <th>POSTED SPEED (km/h)</th> <th>DISTANCE BETWEEN CONVOY VEHICLES</th> </tr> </thead> <tbody> <tr><td>≤40</td><td>50m</td></tr> <tr><td>50</td><td>70m</td></tr> <tr><td>60</td><td>90m</td></tr> <tr><td>70</td><td>110m</td></tr> <tr><td>80</td><td>140m</td></tr> <tr><td>90</td><td>160m</td></tr> <tr><td>100</td><td>200m</td></tr> <tr><td>110</td><td>230m</td></tr> </tbody> </table>			POSTED SPEED (km/h)	DISTANCE BETWEEN CONVOY VEHICLES	≤40	50m	50	70m	60	90m	70	110m	80	140m	90	160m	100	200m	110	230m
POSTED SPEED (km/h)	DISTANCE BETWEEN CONVOY VEHICLES																				
≤40	50m																				
50	70m																				
60	90m																				
70	110m																				
80	140m																				
90	160m																				
100	200m																				
110	230m																				
DRAWN: CAMERON OLSON AWTM CERT. No: KTS-AWTM-21-49061-02 SIGNED: 	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: center;">TABLE A</th> <th colspan="2" style="text-align: center;">BURNING OFF MOBILE WORKS OPERATIONS ALL POSTED SPEEDS WORKERS ON FOOT GREATER THAN 1.2m FROM TRAFFIC</th> </tr> <tr> <th>POSTED SPEED km/h</th> <th>SIGN SPACING m</th> <th>DATE: 26/05/2023</th> <th>REV No: 0</th> </tr> </thead> <tbody> <tr> <td>70</td> <td>140</td> <td rowspan="2" style="background-color: yellow; text-align: center; font-weight: bold;">BURN-23-19</td> <td rowspan="2"></td> </tr> <tr> <td>80</td> <td>160</td> </tr> </tbody> </table>			TABLE A		BURNING OFF MOBILE WORKS OPERATIONS ALL POSTED SPEEDS WORKERS ON FOOT GREATER THAN 1.2m FROM TRAFFIC		POSTED SPEED km/h	SIGN SPACING m	DATE: 26/05/2023	REV No: 0	70	140	BURN-23-19		80	160				
TABLE A		BURNING OFF MOBILE WORKS OPERATIONS ALL POSTED SPEEDS WORKERS ON FOOT GREATER THAN 1.2m FROM TRAFFIC																			
POSTED SPEED km/h	SIGN SPACING m	DATE: 26/05/2023	REV No: 0																		
70	140	BURN-23-19																			
80	160																				