


LEGEND


- WORK AREA
- SAFETY BUFFER
- CONES

**ROAD AUTHORITY SHALL APPROVE
USAGE OF THIS TGS**




GOVERNMENT OF
WESTERN AUSTRALIA

THRESHOLD




CONES MAY BE PLACED ALONG EDGE TO REDUCE LANE WIDTH TO MAX 3.5m



REPEATER SIGNAGE TO BE PLACED EVERY 500m, AT INTERSECTIONS, CURVS AND CRESTS

OR




REPEATER SIGNAGE MAY BE A STAND ALONE 600x600


GENERAL NOTES:

- THIS TGS IS ONLY TO BE USED AS PART OF THIS GENERIC TRAFFIC MANAGEMENT PLAN
- ALL SIGN LOCATIONS ARE TO BE CHECKED PRIOR TO SETOUT AND POSITIONS ADJUSTED TO ALLOW FOR SPECIFIC SITE CONSTRAINTS SUCH AS VEGETATION, OTHER SIGNS, ROADSIDE FURNITURE AND SUFFICIENT SPACE ON SHOULDERS/EMERGENCY LANES.
- THE POSITIONS OF SIGNS, LENGTH OF TAPERS OR MARKING SHALL BE:
 - MINIMUM 10% LESS THAN THE DISTANCES OR LENGTHS GIVEN,
 - MAXIMUM 25% MORE THAN THE DISTANCES OR LENGTHS GIVEN.
- WHEN USING MMS ENSURE TWO 5mm THICK CORE FLUTE SIGNS ARE USED BACK TO BACK IN THE FRAME TO HELP PREVENT THE SIGN FROM BLOWING OUT
- DRIVE SLOWLY CAN BE SWAPPED WITH SMOKE HAZARD, OR BURNING OFF.
- USE OF FOLD UP SIGNS AND SWING SIGNS AND SIGNS ON ONE SIDE OF THE ROAD MAY BE ACCEPTABLE IN NARROW, VERY LOW VOLUME TRACKS <50 VPD
- SUPERVISOR SHALL UNDERTAKE RISK ASSESSMENT TO DETERMINE APPROPRIATE TEMPORARY SPEED RESTRICTION
- THE WORKER SYMBOLIC SIGNS SHALL BE INSTALLED ONLY WHEN ON-FOOT PERSONNEL WILL BE VISIBLE TO PASSING TRAFFIC, OTHERWISE REPLACE WITH BURNING OFF OR SMOKE HAZARD SIGN
- ALL EXISTING SPEED ZONE SIGNAGE WITHIN THE TEMPORARY SPEED ZONE SHALL BE COVERED WITH SUITABLE OPAQUE MATERIAL FOR THE DURATION OF THE WORKS AND COVERS TO BE REMOVED ON COMPLETION OF WORKS EACH DAY UNLESS OTHERWISE NOTED.
- 20km MAX WORK AREA


DISCLAIMER:

IT IS THE RESPONSIBILITY OF THE USER OF THIS TRAFFIC GUIDANCE SCHEME TO CONFIRM THE APPROPRIATENESS OR OTHERWISE FOR THE INTENDED WORK SITE BASED ON RIGOROUS RISK ASSESSMENT AND REVIEW OF THE REQUIREMENTS OF THE AS1742.3 AND MAIN ROADS WA TRAFFIC MANAGEMENT FOR WORKS ON ROADS CoP AND THE AGTTM. ALL RESPONSIBILITY WILL REMAIN WITH THE USER TO ENSURE COMPLIANCE WITH RELEVANT STANDARDS AND THE PROVISION OF THE NECESSARY LEVEL OF PROTECTION FOR WORK PERSONNEL AND WORK SITE.


DRAWN: CAMERON OLSON
AWTM CERT. No: KTS-AWTM-21-49061-02
SIGNED: 

DRAWN: MATTHEW BYRNE
AWTM CERT. No: AUS-AWTM-21-01367-04
SIGNED: 

REINSTATE POSTED SPEED





SIDE ROADS MAY BE SEALED OR UNSEALED AND MAY BE POSTED OR DERESTRICTED




ESCORT VEHICLE

ESCORT AND TAIL VEHICLE SHALL BE DRIVEN BY DEPARTMENT PERSONNEL WITH RADIO COMMUNICATION

OPTIONAL TAIL VEHICLE



TRAFFIC FROM SIDE ROADS MUST BE TAGGED ONTO THE PILOT VEHICLE AND TRAVEL IN THE DIRECTION OF THE PILOT VEHICLE. VEHICLES TRAVELLING IN THE OPPOSITE DIRECTION MUST WAIT FOR THE PILOT VEHICLE TO RETURN.

REINSTATE POSTED SPEED OR USE END 60 IF DERESTRICTED

SECONDARY PREPARE TO STOP SPACING BASED ON ANTICIPATED END OF QUEUE PLUS 2x OF TABLE A SPACING, TRAFFIC CONTROLLERS SHALL MONITOR END OF QUEUE

SECONDARY PREPARE TO STOP SPACING BASED ON ANTICIPATED END OF QUEUE PLUS 2x OF TABLE A SPACING, TRAFFIC CONTROLLERS SHALL MONITOR END OF QUEUE

TABLE A

POSTED SPEED km/h	SIGN SPACING m
70	80
80	80

**BURNING OFF
70km/h - 80km/h POSTED SPEED
WITH TRAFFIC CONTROL AND ESCORT VEHICLE**

DATE: 26/05/2023

REV No: 0

BURN-23-18