


Legend

 Work Area

Road Authority shall approve usage of this TGS.



Very low traffic road/track.  
Less than 10 VPD



GENERAL NOTES:


- 1. This TGS is only to be used as part of the DBCA Generic Traffic Management Plan. To be implemented for emergency road closures. To be authorised by road authority prior to implementation.
- 2. All sign locations are to be checked prior to setout and positions adjusted to allow for specific site constraints such as vegetation, other signs, roadside furniture and sufficient space on shoulders/emergency lanes.
- 3. The positioning of signs, lengths of tapers or markings shall be:
  - a) Minimum 10% less than the distances or lengths given.
  - b) Maximum 25% more than the distances or lengths given.
- 4. When using MMS two 5mm thick core flute signs back to back in the MM frame to help prevent the sign from blowing out.
- 5. Double up closure tape if required.

DISCLAIMER:

It is the responsibility of the user of this traffic guidance scheme to confirm the appropriateness or otherwise for the intended work site based on rigorous risk assessment, review of the requirements of AS1742.3 and Main Roads WA Traffic Management for Works on Roads CoP and AGGTM. All responsibility will remain with the user to ensure compliance with relevant standards and the provision of the necessary level of protection for work personnel and work site.

Drawn: Cheryl Johnson  
AWTM Cert. No: KTS-AWTM-19-47786-01  
Signed: *Cheryl Johnson*

Reviewed by: Brad Brooksby  
AWTM Cert. No: AUS-AWTM-16-1183-05  
Signed: *Brad Brooksby*



VALUE OF DIMENSION 'D'	
Speed of Traffic km/h	Dimension 'D' m
55 or less	15
56 to 65	45
70	140
80	160
90	180
100	200
110	220

BURNING OFF  
FULL TRACK  
CLOSURE

DATE: 24/03/2021

REV No: 13

DBCA - 21 - 19